

A DESIGN-BUILD PROJECT

# ROUTE 7 WIDENING AND BRIDGE REHABILITATION OVER DULLES TOLL ROAD AND AIRPORT ACCESS HIGHWAY

## VOLUME I LETTER OF SUBMITTAL ATTACHMENTS TO LETTER OF SUBMITTAL

Prepared for



State Project No.: 0007-029-139, P101, R201, C501, B617, B618  
Federal Project No.: BR-5401 (738) Contract ID Number: C00082135DB77



March 9, 2015



Volume I



**4.1 Letter of Submittal**

March 9, 2015

Mr. Stephen D. Kindy, P.E.  
Alternate Project Delivery Office  
Virginia Department of Transportation  
1401 East Broad Street  
Richmond, VA 23219

**RE: A Design-Build Project, Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road and Airport Access Highway**  
Fairfax County, Virginia  
State Project No.: 0007-029-139, P101, R201, C501, B617, B618  
Federal Project No.: BR-5401(738) Contract ID Number: C00082135DB77

Dear Mr. Kindy:

G.A. & F.C. Wagman, Inc. (Wagman) is pleased to submit one (1) original paper version of our Letter of Submittal, with full supporting documentation, which bear original signatures; and one (1) CD-ROM containing the entire Letter of Submittal along with attachments in a single cohesive Adobe PDF file to the Virginia Department of Transportation (VDOT) to provide Design-Build (DB) services for the Route 7 Widening Project in Fairfax County, VA. We have carefully reviewed the Request for Proposals (RFP), RFP Addendum Numbers 1, 2 & 3, and RFP Questions and Answers; attended the pre-proposal meetings; and visited the site.

**Project Team**

G.A. & F.C. Wagman, Inc. has assembled a strong and efficient team of highly qualified professionals with the necessary expertise to successfully meet the goals and objectives of this project. Wagman has selected Rinker Design Associates, P.C. (RDA) as our lead design firm to provide all engineering services for this project. Wagman and RDA have excellent reputations in the design and construction of similar projects, with proven prior experience in delivering quality D-B projects. Other members of our team include Whitman, Requardt & Associates, LLP; Quinn Consulting Services, Inc.; DMY Engineering Consultants, Inc.; McCormick Taylor, Inc.; and Branch Highways, Inc.

**4.1.1 Offeror’s Official Representative Information.** The full legal name and address of Wagman is as follows:

<b>G.A. &amp; F.C. Wagman, Inc.</b>	Phone: (717) 767-8277
3290 N. Susquehanna Trail, York, PA 17406-9754	Fax: (717) 767-5546

**4.1.2 Declaration of Intent.** As the Offeror, it is Wagman’s intent, if selected, to enter into a contract with VDOT for the Project in accordance with the terms of this respective RFP.

G.A. & F.C. WAGMAN, INC.



3290 N. Susquehanna Trail | Phone: 717-764-8521  
York, PA 17406-9574 | Fax: 717-764-2799

WWW.WAGMAN.COM

EQUAL OPPORTUNITY EMPLOYER

**4.1.3 120-Day Declaration.** Pursuant to RFP Part 1, Section 8.2, we declare that the offer represented by this Letter of Submittal and Attachments will remain in full force and effect for one hundred twenty (120) days after the date the Letter of Submittal and Attachments are actually submitted to VDOT (March 9, 2015).

**4.1.4 Point of Contact Information.** *Mr. David W. Lyle*, Vice President & Division Manager of Wagman's Virginia Operations, is the official point of contact for the Wagman Team for all matters associated with this Letter of Submittal and Attachments. His contact information is as follows:

<b>David W. Lyle, Vice President &amp; Division Manager</b> 26000 Simpson Road, North Dinwiddie, VA 23803	Phone: (804) 778-4444, Fax: (804) 778-4929 Email: <a href="mailto:dwlyle@wagman.com">dwlyle@wagman.com</a>
--	---

**4.1.5 Principal Officer Information.** *Mr. Gregory Andricos, P.E.*, Executive Vice President of Wagman, is the official principal officer of G.A. & F.C. Wagman, Inc. with whom this DB contract with VDOT will be written. His contact information is as follows:

<b>Gregory Andricos, P.E., Executive Vice President</b> 3290 N. Susquehanna Trail, York, PA 17406-9754	Phone: (717) 764-8521, Fax: (717) 767-5457 Email: <a href="mailto:gmandricos@wagman.com">gmandricos@wagman.com</a>
---	---

**4.1.6 Final Completion Date.** In accordance with RFP Section 2.3.1, Wagman proposes a final completion date of September 1, 2017.

**4.1.7 Proposal Payment Agreement.** An executed Proposal Payment Agreement (Attachment 9.3.1) can be found in the Appendix.

**4.1.8 Certification Regarding Debarment Forms.** Certifications for Debarment for both Primary and Lower Tier Transactions have been completed and executed for the Offeror and all subconsultants, subcontractors, and other entities as identified as members of the Wagman Team. These forms can be found in the Appendix.


**4.1.9 Written Statement of Compliance.** Wagman's Letter of Submittal and Attachments are fully compliant with the Design Criteria Table included in the RFP Technical Requirements (Part 2) as Attachment 2.2 and all other requirements of this RFP. Wagman certifies that the proposed limits of construction to include all stormwater management facilities are located within the right-of-way limits shown on the RFP plans with the exception of permanent and temporary easements. Wagman also certifies that our design concept does not require Design Exception and/or Design Waivers unless they are identified or included in the RFP or Addenda.

**4.1.10 DBE Commitment (8%).** Wagman supports the Disadvantaged Business Enterprise (DBE) program and is committed to achieving the eight percent (8%) DBE participation goal for the entire value of the contract.

Wagman and RDA each have long and successful histories of serving VDOT on numerous projects. As a single, integrated DB Team, we will design and construct the Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road and Airport Access Highway DB Project in a manner to ensure the greatest opportunity for success. We will create a transparent working relationship with VDOT and third party stakeholders to promote trust, confidence, and collaboration.

Respectfully,

**G.A. & F.C. WAGMAN, INC.**



David W. Lyle

Vice President & Division Manager



Volume I

---

## 4.2 Attachments to the Letter of Submittal

---


**4.2.1 Organizational Chart and Key Personnel Confirmation.** With the exception of replacing our Construction Manager (CM), Mike Mansfield, P.E. (Wagman) with David Leber (Wagman), Wagman confirms that the information contained in our SOQ remains true and accurate in accordance with RFP Part 1, Section 11.4. The request to replace the CM was submitted and has been approved by VDOT in writing, which is included in the Appendix. The organizational chart (shown on page 4) has been updated (as designated by strike through and yellow highlight) to include the substitution of the CM. Our organizational chart shows the “chain of command” and identifies major functions to be performed and reporting relationships. The solid lines represent reporting relationships, and the dashed lines represent the coordination and communication relationships. The chart also shows that a clear separation exists between QA and QC functions.

### 3.3.2 Organizational Chart and Narrative

**Team Members.** The following firms will support Wagman and RDA on this Project:

- **Quinn Consulting Services, Inc. (QCS)** will provide the Quality Assurance Manager, QA inspection services, and oversight of the QA DBE laboratory (Specialized Engineering).
- **Whitman, Requardt & Associates, LLP (WR&A)** will provide bridge and geotechnical design as well as overlapping support in other areas of design.
- **Branch Highways, Inc. (BHI)**, as an exclusive subcontractor to G.A. & F.C. Wagman, Inc., will provide grading, storm drainage, and utility construction services.
- **DMY Engineering Consultants, Inc. (DMY)** will provide geotechnical drilling and laboratory services for design and Construction QC services.

The Project Team Organizational Chart is located below.



**Functional Relationships and Communication.** The integration of our design and construction staff with VDOT and the project stakeholders throughout the duration of the Project will promote routine and open communication. VDOT’s participation in formal partnering will be requested to foster an atmosphere of trust and transparency between VDOT, the DB team, and project stakeholders. This will encourage open dialogue when issues arise that may jeopardize the success of the Project.

**VDOT:** The Department will coordinate directly with our DBPM as the primary contact for all aspects of design and construction oversight of the Project. Bi-weekly design and weekly construction progress meetings will include discussions on contract administration; safety; schedule updates; conflict resolution; stakeholder concerns; and progress updates for design, construction, and ROW acquisition. Open lines of communication between the QAM and VDOT will assist with monitoring quality assurance oversight.

Our Public Relations Manager (PRM) will conduct Open houses and other informal outreach efforts to allow the public to view plans and discuss concerns through the design and construction process. The DBPM, DM, and CM will be present to answer questions and address possible concerns. We anticipate VDOT’s oversight and support in our coordination efforts with project stakeholders. Our PRM will facilitate informal meetings and outreach to stakeholders to minimize VDOT’s direct efforts associated with public outreach.

Although our DBPM is not the point of contact through procurement, he will serve as VDOT’s single point of contact for all design and construction related issues upon contract execution. Reporting to the DBPM are four primary positions; the QAM, DM, CM, and PRM. This structure, combined with our DBPM’s maintenance of an action item log for potential issues and three-month look-ahead schedule will ensure the Project remains on-schedule and in conformance with VDOT commitments.

The QAM will report to our DBPM, with independent oversight by VDOT. QA Inspectors and Labs will report through the QAM. Our QAM will also monitor the construction QC program to ensure all work and materials, testing, and sampling is performed in accordance with the contract requirements and the “approved for construction” plans and specifications.

**Design:** Our DM will report to the DBPM and coordinate with the CM to develop an efficient and constructible design. He will work with the CM during construction to confirm field conditions meet design assumptions and reevaluate these assumptions if necessary. The Design QA/QC Manager will report to the DM and independently monitor the design QA/QC process. WR&A will all be subcontracted with RDA for their respective services and their individual discipline leads will report to the DM. This structure will ensure effective and efficient design management.

Coordination between the design and construction staff will start during preparation of the technical proposal and continue throughout the Project to incorporate means and methods into the design. Meetings will also include design disciplinary reviews, over the shoulder reviews, and comment resolution meetings with stakeholders.

Name	Yrs Exp	Expertise
Brandon Shock, PE	15	Roadway design, pedestrian access, and TMP
Jeremy Schluskel, PE	18	Bridge, foundation, and retaining wall designs
Nikhil Deshpande, PE	12	Water resource design, hydrology, and hydraulics
Stephen Seay, LS	28	Topographic and boundary surveys and platting
John Myers	14	Coordination with utility companies and cost estimates
Jeff Basford, PE	14	Geotechnical analysis, reports, and recommendations
Janet O’Neill, PWS, PWD	40	NEPA, Wetlands, and VSMP permitting
James Street	38	ROW negotiations and management
Adam Welschenbach, PE, PTOE	11	Traffic analysis, signal design, and TMP
Erik Shively, PE, PTOE	20	Roadway, traffic, and TMP designs

**Construction:** The CM will report to the DBPM and communicate directly with the QAM/DM/PRM and VDOT’s field personnel to provide construction progress updates and verify conformance with the contract documents. He will also communicate with the DM during both to ensure construction is consistent with the project design. Our CM will be on-site for the duration of construction operations and will personally oversee the entire construction team. Construction leads have been identified for Bridges, Grading, Utilities, MOT Coordination, Construction QC, and Safety—all reporting to the CM.

**Table 3.3.2 Experience of Select CONSTRUCTION Staff**

Name	Yrs Exp	Expertise
Joe Nestlerode	38	Bridges
Steve Morris	20	Grading
Sonny Hanks	32	Utilities
Brian Sluder	15	MOT Coordination
Karen Williams	12	Construction QC
Wayne Johnson	21	Safety

Daily coordination meetings between the CM, senior inspectors, and VDOT’s representative will facilitate communication regarding construction progress. Weekly planning and schedule meetings will include the QA and QC team, VDOT representatives, and design team members as necessary. Before each shift, field supervisors will review safety and performance with their crews to establish protocols in upcoming work.

**Executive Task Force Review Committee:** The Executive Task Force Review Committee will coordinate with the DM and the CM to provide a unified and global evaluation of project challenges to ensure that the project’s goals are maintained. They will establish a resolution hierarchy to ensure that solutions are developed and coordinated at the lowest level feasible. Issues will be tracked through the use of a resolution matrix and will be reported to the DBPM for his acceptance and implementation.

Our Executive Task Force Review Committee is composed of vice presidents from our key design and construction team members in order to facilitate quick responses and resolutions. Additionally, they bring extensive experience on DB and complex projects within their areas of expertise.



**4.2.4 Proposal Schedule and Narrative.** The Wagman Team has provided a Proposal Schedule and Proposal Narrative demonstrating our understanding of the complexities and interrelationships of the technical elements of the Project. PDF copies of the Proposal Schedule and narrative as well as a back-up copy of the Proposal Schedule’s source document have been provided on a CD-ROM.

**4.2.4.1 Proposal Schedule.** The Wagman Team has developed a Proposal Schedule (located in Volume II), which takes into account the internal plan reviews, VDOT plan reviews and approvals, environmental permitting and constraints, right-of-way acquisition, utility relocation, construction activities, and QA/QC inspection and testing. Our Final Completion Date of September 1, 2017 is within the required time frame as listed in RFP Section 2.3.1.

The Proposal Schedule depicts the Wagman Team’s proposed overall sequence of work and duration for each work task and deliverable required to complete the Project. The schedule is organized using a hierarchical Work Breakdown Structure (WBS), divided into major phases of the Project.

**4.2.4.2 Proposal Schedule Narrative.** In addition to the technical elements, the narrative also describes the Wagman Team’s plan to accomplish the Work including, but not limited to, the overall sequencing, a description and explanation of the Critical Path, proposed means and methods, and other key assumptions upon which the Proposal Schedule is based.

**Schedule Development**

The Wagman Team has reviewed in detail the scope and schedule requirements outlined in the RFP documents. Numerous site visits and team meetings were planned, pre-proposal meetings were attended, proprietary meeting discussions occurred, and the schedule task force was developed to build a comprehensive schedule for the Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road & Airport Access Highway.

*The Wagman Team is committed to providing VDOT with a completed Project by September 1, 2017.*

**Project Milestones**

Project Milestones		572.0d	25-Jun-15	01-Sep-17
A1000	Notice to Proceed	0.0d	25-Jun-15	
A1010	Construction Start	0.0d	10-Nov-15	
A1020	Substantial Completion of Design	0.0d		29-Mar-16
A1030	Final Completion (Contract = 01-SEP-2017)	0.0d		01-Sep-17
Bridge Milestones		454.0d	07-Dec-15	01-Sep-17
A1070	Start Construction Phase 1 Bridge	0.0d	07-Dec-15	
A1160	Completion of Phase 1	0.0d		24-Aug-16
A1130	Completion of Phase 2	0.0d		28-Feb-17
A1140	Completion of Phase 3	0.0d		07-Aug-17
A9640	Completion of Phase 4	0.0d		01-Sep-17

**Work Breakdown Structure**

The following Work Breakdown Structure (WBS) provided by the Wagman Team integrates all preconstruction activities as well as construction activities for the Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road & Airport Access Highway project into the schedule. The following is a summary overview of the Phases of Construction succeeded by the complete WBS layout.

**Milestones/General Conditions and Preconstruction Activities.** These sections contain all non-construction related activities that are pertinent to the project. The following categories represent these sections:

- **Milestones:** Major project dates to achieve project completion goals.
- **General Conditions:** Project management and punch list items required for the project.
- **Design:** Duration set aside for the preliminary, right-of-way/roadway design, and final design of the project. The design will consist of three phases to facilitate VDOT reviews and approvals to advance the start of construction. Whenever possible, permits required for construction will be obtained in advance of final design. The Wagman Team will work with VDOT during the design using over-the-shoulder reviews and provide comment resolution with all submissions to reduce subsequent review cycles. The design category also includes the following:
  - Structures & Bridges: Preliminary and final design of the Route 7 bridge and the Shared-Use Path structures.
  - Scope Validation: Duration for discussion between VDOT and the Wagman Team for validation and approval of project scope.
  - Survey: Timeframe allowing all necessary surveying for the design and right-of-way acquisition process.
  - Geotechnical: All borings and lab work required to prepare the Geotechnical Reports.
  - VPDES/SWPPP Permitting: Timeframe set aside for permitting.
  - Individual Wetlands Permits: Timeframe set aside for permitting.
  - Right-of-Way Acquisition Services: Necessary activities for the procurement of public and private property for right-of-way.
  - Utility Coordination and Relocation: Necessary activities to relocate utilities including the design, procurement, and construction of utilities that may be affected by construction.

**Construction Activities.** This project has been designed and set up in four phases built around the bridge construction sequencing. Each phases is further subdivided into work areas.

- **Phase I:** Phase I involves the construction of the new bridge structure between the existing bridges as well as the exterior portion of the new bridge structure located on the north side of the existing bridge. This phase is further broken down into two steps:
  - Phase IA is a preparatory step to allow traffic on the Route 7 East Bound Lane (EBL) bridge to be shifted to the right to allow room for Phase I construction. A temporary walkway will be constructed on the outside of the EBL bridge to maintain pedestrian traffic while the existing sidewalk is removed. Traffic will then be shifted to the right utilizing the space where the sidewalk was originally located.
  - Phase IB includes construction of the new bridge substructure and superstructure located between the existing bridges. New utility relocation will be advanced with phased bridge widening for the under-bridge utility relocation. Bridge construction will require multiple crews to maintain the schedule. Abutment and pier construction will occur simultaneously. Pier construction is sequenced to allow traffic shifts on Dulles Toll Road and Dulles Airport Access Road. Pier 2 construction will be sequenced after Pier 1, and Pier 4 construction will be sequenced after Pier 5. Pier construction will require lane closures in accordance with the RFP.

Preliminary construction activities in Phase I will occur prior to Final Design. These preliminary activities include maintenance of traffic (MOT) as well as support of excavation in preparation for the foundation activities. This will allow new construction to begin immediately upon receiving Approved

For Construction (AFC) plans. Roadway work on Route 7 will occur concurrently with bridge construction and will include drainage and pavement required to tie into the Phase I bridge.


- **Phase II:** Phase II involves new construction within the existing Route 7 West Bound Lane (WBL) footprint. WBL traffic will be shifted onto the new structure completed in Phase I to allow Phase II construction to occur. Phase II bridge construction will include excavation, foundations, substructure, superstructure, and pavement approaches. Roadway work and widening in the existing WBL location will occur simultaneously with the bridge construction. Construction of the NW Quadrant and NE Quadrant Shared-Use Paths are scheduled in Phase II; however, work may commence in Phase I.
- **Phase III:** Phase III involves new construction within the existing Route 7 EBL footprint. Vehicular and pedestrian traffic will be shifted onto the completed structure to allow Phase III activities to occur. Phase III bridge construction will include excavation, foundations, substructure, superstructure, and pavement approaches. Roadway work and widening in the existing EBL location will occur simultaneously with the bridge construction. Construction of the SW Quadrant and SE Quadrant Shared-Use Paths are scheduled in Phase III; however, some work activities may commence in previous phases.
- **Phase IV:** Phase IV involves construction of the median between Route 7 WBL and EBL. Traffic will be shifted while this Phase is underway and then re-shifted to its final location at the end of this Phase.

### Project Work Breakdown Structure

		04-Mar-15 15:10	
WBS Code	WBS Name		Total Activities
Rt. 7 DB	Rt. 7 Widening and Bridge Rehab over DTR - WBS		579
Rt. 7 DB.1	Milestones and General Conditions		13
Rt. 7 DB.1.1	Milestones		9
Rt. 7 DB.1.1.1	Project Milestones		4
Rt. 7 DB.1.1.3	Bridge Milestones		5
Rt. 7 DB.1.4	General Conditions		4
Rt. 7 DB.1.4.1	Entire Project		4
Rt. 7 DB.2	Preconstruction		344
Rt. 7 DB.2.1	Design		225
Rt. 7 DB.2.1.1	Structures and Bridges		39
Rt. 7 DB.2.1.1.1	Route 7 Bridge		12
Rt. 7 DB.2.1.1.2	NW Quadrant SUP Underpasses and Headwalls		9
Rt. 7 DB.2.1.1.3	NE Quadrant SUP Underpasses, Headwalls and Retaining Walls		9
Rt. 7 DB.2.1.1.4	SE Quadrant SUP Pedestrian Bridges, Headwalls and Retaining Walls		9
Rt. 7 DB.2.1.2	Scope Validation		3
Rt. 7 DB.2.1.3	Survey		10
Rt. 7 DB.2.1.4	Geotechnical		65
Rt. 7 DB.2.1.4.1	GER 1		12
Rt. 7 DB.2.1.4.2	GER 2		12
Rt. 7 DB.2.1.4.3	GER 3		12
Rt. 7 DB.2.1.4.4	GER 4		12
Rt. 7 DB.2.1.4.5	GER 5		12
Rt. 7 DB.2.1.5	Preliminary Design		15
Rt. 7 DB.2.1.5.1	Roadway Drainage, Landscaping and Noise		7
Rt. 7 DB.2.1.5.2	Traffic		8
Rt. 7 DB.2.1.6	Furrow Plans		23
Rt. 7 DB.2.1.6.1	Roadway Drainage, Landscaping and Noise		8
Rt. 7 DB.2.1.6.2	Traffic		8
Rt. 7 DB.2.1.6.3	Lighting		7
Rt. 7 DB.2.1.7	Final Design		23
Rt. 7 DB.2.1.7.1	Roadway Drainage, Landscaping and Noise		8
Rt. 7 DB.2.1.7.2	Traffic		8
Rt. 7 DB.2.1.7.3	Lighting		7
Rt. 7 DB.2.1.8	VPOES/DA/PPP Permitting		5
Rt. 7 DB.2.1.9	Individual Wetlands Permits		11
Rt. 7 DB.2.1.10	Right of Way Acquisition Services		20
Rt. 7 DB.2.1.11	Utility Coordination and Relocations		9
Rt. 7 DB.2.1.12	Construction Engineering Services		2
Rt. 7 DB.2.3	Construction Submittals		14
Rt. 7 DB.2.4	Acquisition		9
Rt. 7 DB.5	Construction		322
Rt. 7 DB.5.1	Phase 1		111
Rt. 7 DB.5.1.1	Phase 1A		3
Rt. 7 DB.5.1.2	Phase 1B		107
Rt. 7 DB.5.1.2.1	Bridge		76
Rt. 7 DB.5.1.2.1.1	Abutments		24
Rt. 7 DB.5.1.2.1.2	Piers		35
Rt. 7 DB.5.1.2.1.3	Superstructure		14
Rt. 7 DB.5.1.2.3	Roadway Rt. 7		26
Rt. 7 DB.5.1.2.3.1	Sta. 522+00 to 530+99 (West of Bridge)		12
Rt. 7 DB.5.1.2.3.2	Sta. 535+36 to 547+21 (East of Bridge)		12
Rt. 7 DB.5.7	Phase 2		105
Rt. 7 DB.5.7.2	Bridges		35
Rt. 7 DB.5.7.2.3	Abutments		14
Rt. 7 DB.5.7.2.6	Piers		5
Rt. 7 DB.5.7.2.8	Superstructure		15
Rt. 7 DB.5.7.3	SUP		28
Rt. 7 DB.5.7.3.1	NW Quadrant		14
Rt. 7 DB.5.7.3.2	NE Quadrant		14
Rt. 7 DB.5.7.1	Roadway Rt. 7 WBL		37
Rt. 7 DB.5.7.1.8	Sta. 522+00 to 530+99 (West of Bridge)		15
Rt. 7 DB.5.7.1.1	Sta. 535+36 to 547+21 (East of Bridge)		15
Rt. 7 DB.5.7.4	BMP #1		5
Rt. 7 DB.5.8	Phase 3		99
Rt. 7 DB.5.8.3	Bridge		35
Rt. 7 DB.5.8.3.3	Abutments		14
Rt. 7 DB.5.8.3.4	Piers		5
Rt. 7 DB.5.8.3.5	Superstructure		15
Rt. 7 DB.5.8.5	Roadway Rt. 7 EBL		32
Rt. 7 DB.5.8.5.Sta.	Sta. 522+00 to 530+99 (West of Bridge)		15
Rt. 7 DB.5.8.5.1	Sta. 535+36 to 547+21 (East of Bridge)		15
Rt. 7 DB.5.8.2	SUP		27
Rt. 7 DB.5.8.2.1	SW Quadrant		12
Rt. 7 DB.5.8.2.2	SE Quadrant		15
Rt. 7 DB.5.10	Phase 4		7
Rt. 7 DB.5.10.1	Bridge		1
Rt. 7 DB.5.10.2	Roadway		6
Rt. 7 DB.5.10.2.1	Sta. 522+00 to 530+99 (West of Bridge)		1
Rt. 7 DB.5.10.2.2	Sta. 535+36 to 547+21 (East of Bridge)		1

## Calendars

The Wagman Team has incorporated five calendars into the Project Schedule:



- **7 Day:** This calendar holds every day as a working day. This calendar is only attached to non-production activities.
- **Workweek Weather:** This calendar is the base calendar for construction activities. It incorporates a standard workweek, including weather days.
- **Paving:** This calendar is present for applications that are constrained by temperature restrictions by The Department. Additionally, paving operations are further affected by asphalt lay down temperature restrictions and material availability interruptions due to subcontractor plant shut downs. This calendar runs from the end of December to the beginning of March.
- **Grading:** This calendar is present for construction activities related to earthwork. The end of December through the beginning of March are normally difficult months to perform any earthwork related activities. If weather allows, work activities will continue during this calendar period. The schedule will be adjusted as necessary during these months to reflect actual progress.
- **Standard 5-Day Workweek:** This calendar is the base calendar for design activities and incorporates a standard workweek that does not include weather days.

## Critical Path

The critical path for the project runs through the bridge design and construction. It begins with the preparation of the Route 7 bridge plans, which determines when new construction can begin. The critical path runs through the bridge substructure and then into the bridge superstructure. The critical path also includes the tie-ins and traffic switches between the different phases of construction. The critical path ends with final road finishes.

**Critical Path Breakdown**

Rt. 7 Widening and Bridge Rehab over DTR -		Classic WBS Layout		06-Mar-15 14:16	
Activity ID	Activity Name	Planned Duration	Start	Finish	
<b>Rt. 7 Widening and Bridge Rehab over DTR - WBS</b>		<b>572.0d</b>	<b>25-Jun-15</b>	<b>01-Sep-17</b>	
<b>Milestones and General Conditions</b>		<b>572.0d</b>	<b>25-Jun-15</b>	<b>01-Sep-17</b>	
<b>Milestones</b>		<b>572.0d</b>	<b>25-Jun-15</b>	<b>01-Sep-17</b>	
<b>Project Milestones</b>		<b>572.0d</b>	<b>25-Jun-15</b>	<b>01-Sep-17</b>	
A1000	Notice to Proceed	0.0d	25-Jun-15		
A1010	Construction Start	0.0d	10-Nov-15		
A1030	Final Completion (Contract = 01-SEP-2017)	0.0d		01-Sep-17	
<b>Bridge Milestones</b>		<b>267.0d</b>	<b>24-Aug-16</b>	<b>01-Sep-17</b>	
A1160	Completion of Phase 1	0.0d	24-Aug-16		
A1130	Completion of Phase 2	0.0d	28-Feb-17		
A1140	Completion of Phase 3	0.0d	07-Aug-17		
A9640	Completion of Phase 4	0.0d		01-Sep-17	
<b>Preconstruction</b>		<b>179.0d</b>	<b>25-Jun-15</b>	<b>01-Mar-16</b>	
<b>Design</b>		<b>179.0d</b>	<b>25-Jun-15</b>	<b>01-Mar-16</b>	
<b>Structures and Bridges</b>		<b>179.0d</b>	<b>25-Jun-15</b>	<b>01-Mar-16</b>	
<b>Route 7 Bridge</b>		<b>179.0d</b>	<b>25-Jun-15</b>	<b>01-Mar-16</b>	
D1000	Stage I Design (TS&L)	7.0d	25-Jun-15	06-Jul-15	
D1010	SFC Stage I Design (VDOT, FHWA, MWAA, Fairfax)	5.0d	07-Jul-15	13-Jul-15	
D1020	R/C Stage I Design (VDOT, FHWA, MWAA, Fairfax)	16.0d	14-Jul-15	04-Aug-15	
D1030	Stage II Design - Superstructure	65.0d	05-Aug-15	04-Nov-15	
D1040	SFC Stage II Design - Superstructure (VDOT, FHWA, MWAA)	5.0d	05-Nov-15	11-Nov-15	
D1050	R/C Stage II Design - Superstructure (VDOT, FHWA, MWAA)	16.0d	05-Nov-15	27-Nov-15	
D1060	Final Stage II Design	43.0d	30-Nov-15	29-Jan-16	
D1100	SFC Stage II Design (VDOT, FHWA, MWAA, Fairfax)	5.0d	01-Feb-16	05-Feb-16	
D1111	Final Stage II Design (WMATA)	30.0d	01-Feb-16	01-Mar-16	
<b>FI/ROW Plans</b>		<b>99.0d</b>	<b>25-Jun-15</b>	<b>10-Nov-15</b>	
<b>Traffic</b>		<b>99.0d</b>	<b>25-Jun-15</b>	<b>10-Nov-15</b>	
D2400	Prepare Intermediate Traffic Signals, Signing, Pavement Mark	43.0d	25-Jun-15	25-Aug-15	
D2410	SFC Intermediate Plans (Wagman)	7.0d	26-Aug-15	03-Sep-15	
D2420	A/C Intermediate Plans (Wagman)	5.0d	04-Sep-15	11-Sep-15	
D2430	SFC Intermediate Plans (VDOT, FHWA, MWAA, Fairfax)	3.0d	14-Sep-15	16-Sep-15	
D2440	R/C Intermediate Plans (VDOT, FHWA, MWAA, Fairfax)	15.0d	17-Sep-15	07-Oct-15	
A9180	A/C Intermediate Plans	7.0d	08-Oct-15	16-Oct-15	
D2460	R/A Intermediate Plans (VDOT, FHWA, MWAA, Fairfax)	16.0d	19-Oct-15	09-Nov-15	
D2470	AFC MOT Plans and Details	1.0d	10-Nov-15	10-Nov-15	
<b>Construction</b>		<b>393.0d</b>	<b>02-Mar-16</b>	<b>01-Sep-17</b>	
<b>Phase I</b>		<b>126.0d</b>	<b>02-Mar-16</b>	<b>24-Aug-16</b>	
<b>Phase 1B</b>		<b>126.0d</b>	<b>02-Mar-16</b>	<b>24-Aug-16</b>	
A9400	Pier 2 MOT	2.0d	15-Apr-16	18-Apr-16	
<b>Bridge</b>		<b>115.0d</b>	<b>02-Mar-16</b>	<b>09-Aug-16</b>	
<b>Piers</b>		<b>67.0d</b>	<b>02-Mar-16</b>	<b>02-Jun-16</b>	
A6330	Pier 1 Foundation A	7.0d	02-Mar-16	10-Mar-16	
A9240	Pier 1 Foundation B	10.0d	11-Mar-16	24-Mar-16	
A9290	Pier 1 Footing B	5.0d	25-Mar-16	31-Mar-16	
A9340	FRPS Pier 1B	10.0d	01-Apr-16	14-Apr-16	
A6350	SOE Pier 2	7.0d	19-Apr-16	27-Apr-16	
A9250	Pier 2 Foundation B	10.0d	28-Apr-16	11-May-16	
A9300	Pier 2 Footing B	5.0d	12-May-16	18-May-16	
A9370	FRPS Pier 2B	10.0d	19-May-16	02-Jun-16	
<b>Superstructure</b>		<b>48.0d</b>	<b>03-Jun-16</b>	<b>09-Aug-16</b>	
A6470	Erect Girders	10.0d	03-Jun-16	16-Jun-16	
A6480	Install Overhangs	12.0d	10-Jun-16	27-Jun-16	



ABBREVIATIONS

A/C	Address Comments	S/A	Submit for Approval
R/A	Review and Approve	SFC	Submit for Comment
R/C	Review and Comment	FRPS	Fiber, Rebar, Post, Strip

Rt. 7 Widening and Bridge Rehab over DTR -		Classic WBS Layout		06-Mar-15 14:16	
Activity ID	Activity Name	Planned Duration	Start	Finish	
A6490	SIP Deck Forms	5.0d	28-Jun-16	05-Jul-16	
A6500	Deck Rebar	6.0d	05-Jul-16	13-Jul-16	
A6510	Pour Deck	5.0d	14-Jul-16	20-Jul-16	
A6520	Deck Curing	5.0d	21-Jul-16	27-Jul-16	
A9150	Strip Overhangs	7.0d	28-Jul-16	05-Aug-16	
A6530	Deck Grooving	2.0d	08-Aug-16	09-Aug-16	
<b>Roadway Rt. 7</b>		<b>11.0d</b>	<b>10-Aug-16</b>	<b>24-Aug-16</b>	
A9120	Bridge Tie-Ins	8.0d	10-Aug-16	19-Aug-16	
A9000	Stripe/Switch Traffic to Phase 2	3.0d	22-Aug-16	24-Aug-16	
<b>Phase 2</b>		<b>134.0d</b>	<b>25-Aug-16</b>	<b>28-Feb-17</b>	
<b>Bridges</b>		<b>122.0d</b>	<b>25-Aug-16</b>	<b>10-Feb-17</b>	
A1440	Remove Exist. Superstr.	15.0d	25-Aug-16	15-Sep-16	
<b>Abutments</b>		<b>39.0d</b>	<b>16-Sep-16</b>	<b>09-Nov-16</b>	
A6550	SOE Abut. A	5.0d	16-Sep-16	22-Sep-16	
A6560	SOE Abut. B	5.0d	16-Sep-16	22-Sep-16	
A6570	Rem. Portion of Abut. A	4.0d	23-Sep-16	28-Sep-16	
A6580	Rem. Portion of Abut. B	4.0d	23-Sep-16	28-Sep-16	
A6590	Drive Pile Abut. A	4.0d	29-Sep-16	04-Oct-16	
A6600	Drive Pile Abut. B	4.0d	29-Sep-16	04-Oct-16	
A6610	Retaining Wall Structure Abut. A	10.0d	05-Oct-16	19-Oct-16	
A6620	Retaining Wall Structure Abut. B	10.0d	05-Oct-16	19-Oct-16	
A6630	FRPS Abut. A Footing	5.0d	20-Oct-16	26-Oct-16	
A6640	FRPS Abut. B Footing	5.0d	20-Oct-16	26-Oct-16	
A6650	FRPS Abut. A Seat	6.0d	27-Oct-16	03-Nov-16	
A6660	FRPS Abut. B Seat	6.0d	27-Oct-16	03-Nov-16	
A6670	Coping Abut. A	4.0d	04-Nov-16	09-Nov-16	
A6680	Coping Abut. B	4.0d	04-Nov-16	09-Nov-16	
<b>Superstructure</b>		<b>67.0d</b>	<b>10-Nov-16</b>	<b>10-Feb-17</b>	
A6640	Erect Girders	10.0d	10-Nov-16	23-Nov-16	
A6650	Install Overhangs	10.0d	17-Nov-16	02-Dec-16	
A6670	FRPS Integral Backwall A	8.0d	28-Nov-16	07-Dec-16	
A6680	SIP Deck Forms	5.0d	05-Dec-16	09-Dec-16	
A6670	Deck Rebar	6.0d	12-Dec-16	19-Dec-16	
A6680	FRPS Integral Backwall B	8.0d	08-Dec-16	19-Dec-16	
A6680	Pour Deck	5.0d	20-Dec-16	27-Dec-16	
A6690	Deck Curing	5.0d	28-Dec-16	05-Jan-17	
A6900	FRPS Parapet	7.0d	06-Jan-17	16-Jan-17	
A6910	Install Railing	5.0d	17-Jan-17	23-Jan-17	
A6920	Install Fence	5.0d	24-Jan-17	30-Jan-17	
A9160	Strip Overhangs	7.0d	31-Jan-17	08-Feb-17	
A6930	Groove Deck	2.0d	09-Feb-17	10-Feb-17	
<b>Roadway Rt. 7 WB.</b>		<b>12.0d</b>	<b>13-Feb-17</b>	<b>28-Feb-17</b>	
A9130	Bridge Tie-Ins	8.0d	13-Feb-17	23-Feb-17	
A9010	Stripe/Switch Traffic to Phase 3	3.0d	24-Feb-17	28-Feb-17	
<b>Phase 3</b>		<b>114.0d</b>	<b>01-Mar-17</b>	<b>07-Aug-17</b>	
A9490	Pier 1 MOT	2.0d	15-Mar-17	16-Mar-17	
A9510	Pier 3 MOT	2.0d	29-Mar-17	30-Mar-17	
A9500	Pier 2 MOT	2.0d	12-Apr-17	13-Apr-17	
<b>Bridge</b>		<b>103.0d</b>	<b>01-Mar-17</b>	<b>21-Jul-17</b>	
A6940	Remove Exist. Superstr.	15.0d	01-Mar-17	21-Mar-17	
<b>Piers</b>		<b>28.0d</b>	<b>17-Mar-17</b>	<b>25-Apr-17</b>	



ABBREVIATIONS

A/C	Address Comments	S/A	Submit for Approval
R/A	Review and Approve	R/C	Request for Comments
R/C	Review and Comment	FRPS	Footing, Railing, Parapet, Strip

Rt. 7 Widening and Bridge Rehab over DTR -		Classic WBS Layout		06-Mar-15 14:16	
Activity ID	Activity Name	Planned Duration	Start	Finish	
A7190	Rehab Pier 1	8.0d	17-Mar-17	25-Mar-17	
A7210	Rehab Pier 3	8.0d	31-Mar-17	11-Apr-17	
A7200	Rehab Pier 2	8.0d	14-Apr-17	25-Apr-17	
<b>Superstructure</b>		<b>63.0d</b>	<b>26-Apr-17</b>	<b>21-Jul-17</b>	
A7240	Erect Girders	10.0d	26-Apr-17	09-May-17	
A7250	Install Overhangs	12.0d	01-May-17	16-May-17	
A9690	FRPS Integral Backwall A	8.0d	10-May-17	19-May-17	
A7260	SIP Deck Forms	5.0d	17-May-17	23-May-17	
A7270	Deck Rebar	6.0d	24-May-17	01-Jun-17	
A9700	FRPS Integral Backwall B	8.0d	22-May-17	01-Jun-17	
A7280	Pour Deck	5.0d	02-Jun-17	08-Jun-17	
A7290	Deck Curing	5.0d	09-Jun-17	15-Jun-17	
A7300	FRPS Parapet	6.0d	16-Jun-17	23-Jun-17	
A7310	Install Railing	5.0d	26-Jun-17	30-Jun-17	
A7320	Install Fence	5.0d	03-Jul-17	10-Jul-17	
A9170	Strip Overhangs	7.0d	11-Jul-17	19-Jul-17	
A7330	Groove Deck	2.0d	20-Jul-17	21-Jul-17	
<b>Roadway Rt. 7 EBL</b>		<b>11.0d</b>	<b>24-Jul-17</b>	<b>07-Aug-17</b>	
A9140	Bridge Tie-Ins	8.0d	24-Jul-17	02-Aug-17	
A9030	Stripe/Switch Traffic to Phase 4	3.0d	03-Aug-17	07-Aug-17	
<b>Phase 4</b>		<b>19.0d</b>	<b>08-Aug-17</b>	<b>01-Sep-17</b>	
<b>Bridge</b>		<b>7.0d</b>	<b>08-Aug-17</b>	<b>16-Aug-17</b>	
A8710	FPSC Median	7.0d	08-Aug-17	16-Aug-17	
<b>Roadway</b>		<b>19.0d</b>	<b>08-Aug-17</b>	<b>01-Sep-17</b>	
A9040	M/I Overlay	3.0d	17-Aug-17	21-Aug-17	
A9050	Final Paving	5.0d	22-Aug-17	28-Aug-17	
A9060	Final Striping	4.0d	28-Aug-17	01-Sep-17	
Sta. 522+00 to 530+99 (West of Bridge)		7.0d	08-Aug-17	16-Aug-17	
A8720	FPSC MS-1A	7.0d	08-Aug-17	16-Aug-17	
Sta. 535+36 to 547+21 (East of Bridge)		7.0d	08-Aug-17	16-Aug-17	
A8730	FPSC MS-2	7.0d	08-Aug-17	16-Aug-17	



ABBREVIATIONS

A/C	Address Comments	SFA	Submit for Approval
R/A	Review and Approve	RFC	Request for Comments
R/C	Review and Comment	FRPS	Forms, Rates, Plans, Notes

## Design

---

The Wagman Team will advance the design from the current RFP documents and incorporate new design elements into final design and construction documents. Design activities will include surveying, roadway design, bridge design, traffic control devices, maintenance of traffic plans, signs, guardrail, pavement markings, drainage design, design of stormwater management facilities, geotechnical investigation including borings and analysis, materials analysis, hydraulic design and pavement design. The project will be delivered by completing three phases of design: preliminary design, right-of-way design, and final design (labeled as Stage 1 and Stage 2 for roadway design, and Final Stage II for structures design). Design-related activities to be performed during each phase are outlined below.

**Preliminary design activities** will focus on expanding the RFP documents and preparing a set of preliminary plans and reports for submission to VDOT for review and approval. The Wagman Team will perform numerous independent studies of the information contained in the RFP documents to confirm that the information provided to date is correct and suitable for use in designing the project. These additional studies will include performing supplemental field surveying to confirm horizontal and vertical control of key project features verifying type and location of existing subsurface utilities; performing legal research to confirm existing right-of-way and property limits; and performing a thorough geotechnical field investigation to confirm geotechnical conditions for the bridge foundation and roadway design. The findings of these studies will be summarized in a series of reports and, if discrepancies occur between the information in the RFP documents and the Wagman Team studies, these results will be presented to VDOT for review and evaluation as outlined in the Scope Validation process for the project. Preliminary roadway plans will be developed including performing geometric design; preparing cross sections and defining limits of construction; completing stormwater management and erosion and sediment control design; preparing plans for traffic control devices as well as a Transportation Management Plan; and completing the preliminary bridge plans working closely with the geotechnical engineers. Required right-of-way limits will be evaluated and depicted on the plans, and preliminary utility relocation plans will be prepared.

**Right-of-way/roadway design submittal** will occur after receiving preliminary plan approval from VDOT. The right-of-way, environmental coordination and approval, and utility relocation plan activities will be separated and developed for individual submissions to VDOT and other regulatory agencies for review and approval. The preliminary bridge and roadway plans will be fully detailed and ready for construction.

**Final design submittal** will occur after receiving right-of-way/roadway design plan approval from VDOT. The Wagman Team will submit the final design plans and reports to VDOT for review and approval.

## Environmental Coordination and Approvals

---

Preliminary environmental activities will begin shortly after receiving Notice to Proceed and will include a thorough environmental evaluation and confirmation of the information provided in the RFP documents. The Wagman Team will prepare a comprehensive environmental management plan that includes a matrix of environmental commitments and compliance requirements; identifies milestone dates and integrates those into the project schedule; identifies the responsible party; and summarizes requirements.

Final environmental activities will begin immediately after receiving preliminary plan approval from VDOT. At this point in the design, the footprint for the project will be firmly established and the Wagman Team will identify the final environmental impacts required to construct the project in its entirety. The Wagman Team will strive to avoid and minimize environmental impacts during design development and construction. A Stormwater Pollution Prevention Plan (SWPPP) will be developed and the registration statement for the Virginia Stormwater Management Permit will be submitted immediately following the SWPPP development.

## Right-of-Way

---

The Wagman Team will evaluate the proposed right-of-way, permanent easements, and temporary easements as shown on the plans. If changes are required, either due to a change in the required right-of-way or a change based on the results of legal research, the Team will prepare updated preliminary right-of-way plans and a right-of-way data sheet and will submit to VDOT for review and approval. Preliminary right-of-way activities will begin after receiving Notice to Proceed. The Wagman Team will begin performing the legal research for the identified parcels on the preliminary plans at the same time that our survey crew is validating the survey information provided in the RFP package.

## Schedule & Project Management

---

The schedule is the most important tool in the construction management process and is an efficient method to communicate the intended sequence and progress of the project to the construction team as well as the project stakeholders. The schedule is an extremely useful and productive planning tool. The Wagman Team takes pride in our detailed advance planning for safe and efficient execution of the work. Our Construction Managers, Superintendents, Safety Professionals, and Craft Supervisors use this critical tool as the first step in developing Activity Hazard Analyses and Activity Work Plans. In addition to early planning, the schedule is used to monitor the project's progress and help identify potential deficiencies and problem areas before they develop into a critical impact.

The project management team will continually review and monitor the schedule and use the information gathered to develop mitigation strategies for any activities that are identified as potential impacts. This proactive approach will ensure that the project continues to move forward and that any potential delays are addressed immediately. A variety of different tools will be utilized to assist with this process, including but not limited to the following:

- Weekly schedule and task force meetings between the engineering and construction team members during the design phase
- Weekly construction scheduling meetings throughout the duration of the construction process with the construction team (including management)
- Monthly progress meetings to include all project stakeholders, project team members, and subcontractors
- Three-week look ahead schedules
- RFI logs
- Submittal logs
- Work plans
- Subcontract/purchase order logs
- Shop drawing tracking logs
- Weekly manpower and equipment reviews.

All of the above referenced tools will be utilized simultaneously to provide a current and realistic picture of the progress and status at any given time. Information will be presented at meetings to all who are involved for the opportunity to discuss and address any concerns in front of all that are affected. This keeps the line of communication open and allows resolutions and recovery strategies to be developed at an early stage, therefore preventing any further conflict.

---

## Schedule Recovery

---

Unexpected issues and unforeseen conditions are a possibility during the construction process. The Wagman Team includes many experienced and well-respected members in the DB field with the ability to recognize and react to any issues. The Wagman Team will aggressively manage the project and, if needed, mitigate any issues that affect the construction schedule. If necessary, a schedule recovery strategy will be developed, immediately implemented, and closely monitored until the schedule is recovered.

---

## Subcontractor & Material Supplier Scheduling

---

Subcontractors & Material Suppliers are a critical part of the project schedule. The Wagman Team will closely evaluate each subcontractor and supplier based on quality, performance, and reputation. Beginning with the initial subcontract paperwork, each subcontractor will be intimately involved with every aspect of the project schedule, and their input will be vital. Suppliers will go through a similar process. This includes progress meetings, weekly look-ahead schedules, material submittals, and recovery strategies if needed. Accountability is the key to effective subcontractor and supplier management, and it will be perfectly clear that subcontractors and suppliers will be held accountable for all aspects of their work from quality to schedule.

**4.2.4 Proposal Schedule in electronic format (CD-ROM).** In addition to the hard copy located in Volume II, the Wagman Team has provided a copy of the Proposal Schedule and narrative in PDF format as well as a back-up copy of the Proposal Schedule's source document in XER format on a CD-ROM, which is located in the sleeve below.



Volume I

**4.0.1.1 (Attachment 4.0.1.1)**  
Letter of Submittal Attachments  
Checklist

**ATTACHMENT 4.0.1.1**

**Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road and Airport Access Highway**

**LETTER OF SUBMITTAL AND ATTACHMENTS CHECKLIST**

Offerors shall furnish a copy of this Letter of Submittal Checklist, with the page references added, with the Letter of Submittal.

<b>Technical Proposal Component</b>	<b>Form (if any)</b>	<b>RFP Part 1 Cross Reference</b>	<b>Page Reference</b>
<b>Letter of Submittal and Attachments Checklist</b>	Attachment 4.0.1.1	Section 4.0.1.1	<b>Volume I Appendix</b>
<b>Acknowledgement of RFP, Revisions, and/or Addenda</b>	Attachment 3.6 (Form C-78-RFP)	Sections 3.6, 4.0.1.1	<b>Volume I Appendix</b>
<b>Letter of Submittal</b>	NA	Sections 4.1	<b>I-1-2</b>
Letter of Submittal on Offeror's letterhead	NA	Section 4.1.1	<b>I-1, I-2</b>
Offeror's official representative information	NA	Section 4.1.1	<b>I-1</b>
Authorized representative's original signature	NA	Section 4.1.1	<b>I-2</b>
Declaration of intent	NA	Section 4.1.2	<b>I-1</b>
120 day declaration	yes	Section 4.1.3	<b>I-2</b>
Point of Contact information	yes	Section 4.1.4	<b>I-2</b>
Principal Officer information	NA	Section 4.1.5	<b>I-2</b>
Final Completion Date	NA	Section 4.1.6	<b>I-2</b>
Proposal Payment Agreement or Waiver of Proposal Payment	Attachment 9.3.1 or 9.3.2	Section 4.1.7	<b>Volume I Appendix</b>
Certification Regarding Debarment Forms	Attachment 11.8.6(a) Attachment 11.8.6(b)	Section 4.1.8	<b>Volume I Appendix</b>
Written statement that Offeror's proposed concept included in the Attachments to the LOS is fully compliant with the Design Criteria Table and all other requirements of the RFP	NA	Section 4.1.9	<b>I-2</b>
Certification that the proposed limits of construction are located within the right-of-way limits shown on RFP plans	NA	Section 4.1.9	<b>I-2</b>
Written statement of percent DBE participation	NA	Section 4.1.10	<b>I-2</b>

## ATTACHMENT 4.0.1.1

### Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road and Airport Access Highway

#### LETTER OF SUBMITTAL AND ATTACHMENTS CHECKLIST

Technical Proposal Component	Form (if any)	RFP Part 1 Cross Reference	Page Reference
<b>Attachments to the Letter of Submittal</b>	NA	Section 4.2	<b>I-3</b>
Confirmation that the information provided in the SOQ submittal remains true and accurate or indicates that any requested changes were previously approved by VDOT	NA	Section 4.2.1	<b>I-3</b>
Organizational chart with any updates since the SOQ submittal clearly identified	NA	Section 4.2.1	<b>I-4</b>
Revised narrative when organizational chart includes updates since the SOQ submittal	NA	Section 4.2.1	<b>I-3</b>
Conceptual Roadway Plans – Plan View	NA	Section 4.2.2	<b>II-1 – II-24</b>
Conceptual Roadway Plans – Typical Sections	NA	Section 4.2.2	<b>II-25 – II-27</b>
Conceptual Structural Plans – Elevation View	NA	Section 4.2.3	<b>II-28</b>
Conceptual Roadway <b>Structural</b> Plans – Transverse Section	NA	Section 4.2.3	<b>II-29 – II-30</b>
Conceptual Roadway <b>Structural</b> Plans – Abutment Configuration	NA	Section 4.2.3	<b>II-31 – II-36</b>
<b>Proposal Schedule</b>	NA	Section 4.2.4	
Proposal Schedule	NA	Section 4.2.4.1	<b>II-37 – II-46</b>
Proposal Schedule Narrative	NA	Section 4.2.4.2	<b>I-7 – I-17</b>
Proposal Schedule in electronic format (CD-ROM)	NA	Section 4.2.4	<b>I-17 in CD sleeve</b>

**3.6 (Attachment 3.6)**  
Acknowledgement of Receipt of RFP,  
Revisions, and/or Addenda

**ATTACHMENT 3.6****COMMONWEALTH OF VIRGINIA  
DEPARTMENT OF TRANSPORTATION**

RFP NO. C00082135DB77  
 PROJECT NO.: 0007-029-139, P101, R201, C501, B617, B618

**ACKNOWLEDGEMENT OF RFP, REVISION AND/OR ADDENDA**

Acknowledgement shall be made of receipt of the Request for Proposals (RFP) and/or any and all revisions and/or addenda pertaining to the above designated project which are issued by the Department prior to the Letter of Submittal submission date shown herein. Failure to include this acknowledgement in the Letter of Submittal may result in the rejection of your proposal.

By signing this Attachment 3.6, the Offeror acknowledges receipt of the RFP and/or following revisions and/or addenda to the RFP for the above designated project which were issued under cover letter(s) of the date(s) shown hereon:

1. Cover letter of September 19, 2014 – RFP  
(Date)
2. Cover letter of February 13, 2015 – Addendum #1  
(Date)
3. Cover letter of March 3, 2015 – Addendum #2  
(Date)
4. Cover letter of March 5, 2015 – Addendum #3  
(Date)



SIGNATURE

March 9, 2015

DATE

David W. Lyle

PRINTED NAME

Vice President & Division Manager

TITLE



**ATTACHMENT 9.3.1**  
**PROPOSAL PAYMENT AGREEMENT**

**THIS PROPOSAL PAYMENT AGREEMENT** (this “Agreement”) is made and entered into as of this 9th day of March, 2015, by and between the Virginia Department of Transportation (“VDOT”), and G.A. & F.C. Wagman, Inc. (“Offeror”).

**WITNESSETH:**

**WHEREAS**, Offeror is one of the entities who submitted Statements of Qualifications (“SOQs”) pursuant to VDOT’s **May 13, 2014** Request for Qualifications (“RFQ”) and was invited to submit proposals in response to a Request for Proposals (“RFP”) for the **Route 7 Widening and Bridge Rehabilitation over Dulles Toll Road and Airport Access Highway, Project No. 0007-029-139, P101, R201, C501, B617, B618** (“Project”), under a design-build contract with VDOT (“Design-Build Contract”); and

**WHEREAS**, as part of the procurement process for the Project, Offeror has already provided and/or furnished to VDOT, and may continue to provide and/or furnish to VDOT, certain intellectual property, materials, information and ideas, including, but not limited to, such matters that are: (a) conveyed verbally and in writing during proprietary meetings or interviews; and (b) contained in, related to or associated with Offeror’s proposal, including, but not limited to, written correspondence, designs, drawings, plans, exhibits, photographs, reports, printed material, tapes, electronic disks, or other graphic and visual aids (collectively “Offeror’s Intellectual Property”); and

**WHEREAS**, VDOT is willing to provide a payment to Offeror, subject to the express conditions stated in this Agreement, to obtain certain rights in Offeror’s Intellectual Property, provided that Offeror submits a proposal that VDOT determines to be responsive to the RFP (“Offeror’s Proposal”), and either (a) Offeror is not awarded the Design-Build Contract; or (b) VDOT cancels the procurement or decides not to award the Design-Build Contract to any Offeror; and

**WHEREAS**, Offeror wishes to receive the payment offered by VDOT, in exchange for granting VDOT the rights set forth in this Agreement.

**NOW, THEREFORE**, in consideration of the mutual covenants and agreements set forth in this Agreement and other good and valuable consideration, the receipt and adequacy of which are acknowledged by the parties, the parties agree as follows:

**1. VDOT's Rights in Offeror's Intellectual Property.** Offeror hereby conveys to VDOT all rights, title and interest, free and clear of all liens, claims and encumbrances, in Offeror's Intellectual Property, which includes, without restriction or limitation, the right of VDOT, and anyone contracting with VDOT, to incorporate any ideas or information from Offeror's Intellectual Property into: (a) the Design-Build Contract and the Project; (b) any other contract awarded in reference to the Project; or (c) any subsequent procurement by VDOT. In receiving all rights, title and interest in Offeror's Intellectual Property, VDOT is deemed to own all intellectual property rights, copyrights, patents, trade secrets, trademarks, and service marks in Offeror's Intellectual Property, and Offeror agrees that it shall, at the request of VDOT, execute all papers and perform all other acts that may be necessary to ensure that VDOT's rights, title and interest in Offeror's Intellectual Property are protected. The rights conferred herein to VDOT include, without limitation, VDOT's ability to use Offeror's Intellectual Property without the obligation to notify or seek permission from Offeror.

**2. Exclusions from Offeror's Intellectual Property.** Notwithstanding Section 1 above, it is understood and agreed that Offeror's Intellectual Property is not intended to include, and Offeror does not convey any rights to, the Escrow Proposal Documents submitted by Offeror in accordance with the RFP.

**3. Proposal Payment.** VDOT agrees to pay Offeror the lump sum amount of [*written number*] and 00/100 Dollars (\$[*numerical*].00) ("Proposal Payment"), which payment constitutes payment in full to Offeror for the conveyance of Offeror's Intellectual Property to VDOT in accordance with this Agreement. Payment of the Proposal Payment is conditioned upon: (a) Offeror's Proposal being, in the sole discretion of VDOT, responsive to the RFP; (b) Offeror complying with all other terms and conditions of this Agreement; and (c) either (i) Offeror is not awarded the Design-Build Contract, or (ii) VDOT cancels the procurement or decides not to award the Design-Build Contract to any Offeror.

**4. Payment Due Date.** Subject to the conditions set forth in this Agreement, VDOT will make payment of the Proposal Payment to the Offeror within forty-five (45) days after the later of: (a) notice from VDOT that it has awarded the Design-Build Contract to another Offeror; or (b) notice from VDOT that the procurement for the Project has been cancelled and that there will be no Contract Award.

**5. Effective Date of this Agreement.** The rights and obligations of VDOT and Offeror under this Agreement, including VDOT's ownership rights in Offeror's Intellectual Property, vests upon the date that Offeror's Proposal is submitted to VDOT. Notwithstanding the above, if Offeror's Proposal is determined by VDOT, in its sole discretion, to be nonresponsive to the RFP, then Offeror is deemed to have waived its right to obtain the Proposal Payment, and VDOT shall have no obligations under this Agreement.

**6. Indemnity.** Subject to the limitation contained below, Offeror shall, at its own expense, indemnify, protect and hold harmless VDOT and its agents, directors, officers, employees, representatives and contractors from all claims, costs, expenses, liabilities, demands, or suits at law or equity (“Claims”) of, by or in favor of or awarded to any third party arising in whole or in part from: (a) the negligence or wilful misconduct of Offeror or any of its agents, officers, employees, representatives or subcontractors; or (b) breach of any of Offeror’s obligations under this Agreement, including its representation and warranty under Section 8 hereof. This indemnity shall not apply with respect to any Claims caused by or resulting from the sole negligence or wilful misconduct of VDOT, or its agents, directors, officers, employees, representatives or contractors.

**7. Assignment.** Offeror shall not assign this Agreement, without VDOT's prior written consent, which consent may be given or withheld in VDOT’s sole discretion. Any assignment of this Agreement without such consent shall be null and void.

**8. Authority to Enter into this Agreement.** By executing this Agreement, Offeror specifically represents and warrants that it has the authority to convey to VDOT all rights, title, and interest in Offeror’s Intellectual Property, including, but not limited to, those any rights that might have been vested in team members, subcontractors, consultants or anyone else who may have contributed to the development of Offeror’s Intellectual Property, free and clear of all liens, claims and encumbrances.

**9. Miscellaneous.**

a. Offeror and VDOT agree that Offeror, its team members, and their respective employees are not agents of VDOT as a result of this Agreement.

b. Any capitalized term used herein but not otherwise defined shall have the meanings set forth in the RFP.

c. This Agreement, together with the RFP, embodies the entire agreement of the parties with respect to the subject matter hereof. There are no promises, terms, conditions, or obligations other than those contained herein or in the RFP, and this Agreement shall supersede all previous communications, representations, or agreements, either verbal or written, between the parties hereto.

d. It is understood and agreed by the parties hereto that if any part, term, or provision of this Agreement is by the courts held to be illegal or in conflict with any law of the Commonwealth of Virginia, validity of the remaining portions or provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Agreement did not contain the particular part, term, or provisions to be invalid.

e. This Agreement shall be governed by and construed in accordance with the laws of the Commonwealth of Virginia.

**IN WITNESS WHEREOF**, this Agreement has been executed and delivered as of the day and year first above written.

VIRGINIA DEPARTMENT OF TRANSPORTATION

By: \_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

*[Insert Offeror's Name]*

By: **G.A. & F.C. Wagman, Inc.** \_\_\_\_\_

Name: *David W. Lyle* David W. Lyle

Title: Vice President & Division Manager

**4.1.8 (Attachments 11.8.6(a) & (b))**  
Certification Regarding Debarment  
Forms

**ATTACHMENT NO. 11.8.6(a)**

**CERTIFICATION REGARDING DEBARMENT  
PRIMARY COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

1) The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency.


b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; and have not been convicted of any violations of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification, or destruction of records, making false statements, or receiving stolen property;

c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1) b) of this certification; and

d) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

2) Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

  
Signature

3/9/2015  
Date

Vice President & Division Manager  
Title

G.A. & F.C. Wagman, Inc.  
Name of Firm

ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

  
\_\_\_\_\_  
Signature

3/6/2015  
\_\_\_\_\_  
Date

Director of Business Development/  
\_\_\_\_\_  
Title Principal

Rinker Design Associates, P.C.  
\_\_\_\_\_  
Name of Firm

ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

 March 2, 2015  
Signature Date President  
Title

Quinn Consulting Services, Inc.  
Name of Firm


ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

- 1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
  
- 2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

 March 4, 2015 President  
Signature Date Title

Specialized Engineering  
Name of Firm

ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

- 1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
  
- 2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

  
Signature \_\_\_\_\_ Date 3/3/2015

Vice President, Design Build Services  
Title

Branch Highways, Inc.  
Name of Firm


ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

- 1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
  
- 2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

  
\_\_\_\_\_  
Signature

3/2/15  
\_\_\_\_\_  
Date

PARTNER  
\_\_\_\_\_  
Title

WHITMAN, REQUARDT AND ASSOCIATES, LLP  
\_\_\_\_\_  
Name of Firm

ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618 .

Contract ID: C00082135DB77

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

 3/2/2015 Vice President  
Signature Date Title

DMY Engineering Consultants Inc.  
Name of Firm

ATTACHMENT NO. 11.8.6(b)

**CERTIFICATION REGARDING DEBARMENT  
LOWER TIER COVERED TRANSACTIONS**

Project: 0007-029-139, P101, R201, C501, B617, B618  
Contract ID: C00082135DB77

- 1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.
  
- 2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this form.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

  
Signature \_\_\_\_\_

3/3/2015  
Date

Chief Executive Officer  
Title

McCormick Taylor, Inc.  
Name of Firm





# COMMONWEALTH of VIRGINIA

DEPARTMENT OF TRANSPORTATION  
1401 EAST BROAD STREET  
RICHMOND, VIRGINIA 23219 2000

**Charles A. Kilpatrick, P.E.**  
Commissioner

March 5, 2015

Mr. David Lyle  
G.A. & F.C. Wagman, Inc.  
Virginia Operations  
26000 Simpson Road  
North Dinwiddie, VA 23803

**Subject: Route 7 Widening and Bridge Reconstruction over Dulles Road and Airport  
Access Highway Project  
Request for Key Personnel Change – Construction Manager**

Mr. Lyle:

Thank you for your team's letter, dated February 23, 2015, requesting a change in the Key Personnel for the project referenced above, and providing information regarding your request to change your team's Construction Manager. Your letter specifically mentions that Mr. Michael Mansfield, P.E. was listed as a Construction Manager on another project pursuit which was successfully procured by G.A. & F.C. Wagman, Inc. in the previous month. G.A. & F.C. Wagman, Inc. was in pursuit of that project since the summer of 2014 and received notice of award in January 2015.


After careful consideration of the information provided by G.A. & F.C. Wagman, Inc. and in accordance with Section 7.1.15 and Section 11.1 of the RFP which allows VDOT to approve a change in the Key Personnel under extraordinary circumstances, VDOT has determined it will grant the substitution of Mr. David Leber for Mr. Michael Mansfield, P.E. as the proposed Construction Manager for your team.

Sincerely,

A handwritten signature in black ink that reads "Stephen D. Kindy".

Stephen D. Kindy, P.E.  
Senior Project Delivery Engineer






A DESIGN-BUILD PROJECT

# ROUTE 7 WIDENING

## AND BRIDGE REHABILITATION OVER DULLES TOLL ROAD AND AIRPORT ACCESS HIGHWAY

### VOLUME II DESIGN CONCEPT GRAPHICS PROPOSAL SCHEDULE



Prepared for



State Project No.: 0007-029-139, P101, R201, C501, B617, B618  
Federal Project No.: BR-5401 (738) Contract ID Number: C00082135DB77



March 9, 2015




Volume II

PROJECT MANAGER: *Act* *ur* *Babman, PE* (703) 259-1940 (N.Wax District)  
SURVEYED BY, DATE: *Woolpert, Inc.*; February 6, 2013  
DESIGN BY: *Blinker Design Associates*  
SUBSURFACE UTILITY BY, DATE: *Woolpert, Inc.*; January 22, 2013

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	3

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



**ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.**

**LEGEND**

	Proposed Pavement Milling and Overlay
	Proposed Full Depth Pavement
	Demolition of Pavement

Note: Figures in brackets and dot-dashed lines denote Permanent Easements.  
 [C] --- Denotes Construction Limits In Cuts  
 [F] --- Denotes Construction Limits In Fills

**REFERENCES (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)**

Construction Alignment Data	IG(1)-IG(4)
Typical Sections	2A
Route 7 EB & WB Profile	3A
Shared Use Path Profile	3A(1)
Utility Owners	1E
Property Owners	1E



SCALE 1" = 25'




PROJECT	0007-029-139
SHEET NO.	3

PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	3A

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
Glen Allen, Virginia  
Civil Engineer




PROJECT 0007-029-139  
SHEET NO. 3A

PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	3A(1)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT


Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer



PROJECT MANAGER: Actric Babman, PE (703) 259-1940 (Linn District)  
SURVEYED BY, DATE: Woolpert, Inc., February 6, 2013  
DESIGN BY: Blinker Design Associates  
SUBSURFACE UTILITY BY, DATE: Woolpert, Inc., January 22, 2013

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	4

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



**ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.**


**LEGEND**

	Proposed Pavement Milling and Overlay
	Proposed Full Depth Pavement
	Demolition of Pavement

Note: Figures in brackets and dot-dashed lines denote Permanent Easements.  
C --- Denotes Construction Limits in Cuts  
F --- Denotes Construction Limits in Fills

**REFERENCES (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)**

Construction Alignment Data IG(1)-IG(4)	
Typical Sections	2A
Route 7 EB & WB Profile	4A
Shared Use Path Profiles	4A(1)
Ramp Profiles	4A(2)
Utility Owners	IE
Property Owners	IE



PROJECT	0007-029-139	SHEET NO.	4
---------	--------------	-----------	---




3/4/2015

PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	4A

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer








PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	4A(2)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer




PROJECT MANAGER: *Adrian Rotman, PE* (703) 259-1940 (Work District)  
SURVEYED BY, DATE: *Woodpeck, Inc.* February 6, 2013  
DESIGN BY: *Parsons Brinckerhoff, Inc.*  
SUBSURFACE UTILITY BY, DATE: *Woodpeck, Inc.* January 22, 2013

THESE PLANS ARE UNFINISHED AND UNAPPROVED AND ARE NOT TO BE USED FOR ANY TYPE OF CONSTRUCTION OR THE ACQUISITION OF RIGHT OF WAY.

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, B617, B618, R201, P101	5

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



MATCH LINE SHEET 4 - STA 527+00

MATCH LINE SHEET 6 - STA 534+00

ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.

C --- Denotes Construction Limits In Cuts  
F --- Denotes Construction Limits In Fills

**LEGEND**  
 Proposed Pavement Milling and Overlay  
 Proposed Full Depth Pavement  
 Demolition of Pavement

Potential Material Laydown Area (to be graded and permanently stabilized prior to contract completion)

Note: Figures in brackets and dot-dashed lines denote Permanent Easements.

REFERENCES  
(PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)

Construction Alignment Data	IG(1)-IG(4)
Typical Sections	2A
Route 7 EB & WB Profile	5A
Shared Use Path Profiles	5A(1)
Ramp Profiles	5A(2)
Utility Owners	1E
Property Owners	1E



BRIDGING GENERATIONS - SINCE 1902  
SCALE  
0 25' 50'


PROJECT	SHEET NO.
0007-029-139	5

PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	5A

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer





STA - 532+85.00  
 EL - 391.37  
 SSD - 498'  
 ex - 0.48'  
 K - 59  
 L - 150.00  
 V - 40mph

STA - 530+60.00  
 EL - 388.78  
 ex - 0.39'  
 K - 78  
 L - 155.00  
 V - 40 mph

STA - 532+74.48  
 EL - 391.61  
 SSD - 498'  
 ex - 0.48'  
 K - 59  
 L - 150.00  
 V - 40 mph

STA - 530+49.48  
 EL - 389.02  
 ex - 0.31'  
 K - 98  
 L - 155.00  
 V - 40 mph





PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	5A(1)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer





PROJECT MANAGER Actur Babman, PE (703) 259-1940 (Nava District)  
 SURVEYED BY, DATE Woolpert, Inc. February 6, 2013  
 DESIGN BY Rinker Design Associates  
 SUBSURFACE UTILITY BY, DATE Woolpert, Inc. January 22, 2013

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	5A(2)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 Civil Engineer




PROJECT MANAGER: *Act/ur Babman, PE (703) 259-1940 (L'noxia District)*  
SURVEYED BY, DATE: *Woolpert, Inc. February 6, 2013*  
DESIGN BY: *Blinker Design Associates*  
SUBSURFACE UTILITY BY, DATE: *Woolpert, Inc. January 22, 2013*

**ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.**

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, B617, B618, R201, P101	6

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



**LEGEND**

	Proposed Pavement Milling and Overlay
	Proposed Full Depth Pavement
	Demolition of Pavement

Note: Figures in brackets and dot-dashed lines denote Permanent Easements.

	Denotes Construction Limits in Cuts		Potential Material Laydown Area (to be graded and permanently stabilized prior to contract completion)
	Denotes Construction Limits in Fills		

**REFERENCES (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)**

Construction Alignment Data IG(1)-IG(4)	
Typical Sections	2B
Route 7 EB & WB Profile	6A
Shared Use Path Profiles	6A(1)
Ramp Profiles	6A(2)
Radio Tower Profile	6A(3)
Utility Owners	1E
Property Owners	1E



SCALE 0 25' 50'



PROJECT	SHEET NO.
0007-029-139	6

PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6A

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer






PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6A(1)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer






PROJECT MANAGER *Act'ur Babman, PE* (703) 259-1940 (Nava District) ---  
SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013* ---  
DESIGN BY *Blinker Design Associates* ---  
SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013* ---

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6A(2)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
Glen Allen, Virginia  
Civil Engineer





PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6A(3)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer




PROJECT: Manager: *Act/ur Babman, PE (703) 259-1940 (L'noxia District)*  
 SURVEYED BY: DATE: *Woolpert, Inc. February 6, 2013*  
 DESIGN BY: *Blinker Design Associates*  
 SUBSURFACE UTILITY BY: DATE: *Woolpert, Inc. January 22, 2013*

**ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.**

**THESE PLANS ARE UNFINISHED AND UNAPPROVED AND ARE NOT TO BE USED FOR ANY TYPE OF CONSTRUCTION OR THE ACQUISITION OF RIGHT OF WAY.**

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6C

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



Curve HA\_RAMPC-1  
 PI = 1175.02  
 DELTA = 27° 48' 01.2" (RT)  
 D = 1235.33'  
 T = 12.60'  
 L = 220.77'  
 R = 455.00'  
 PC = 1062.42  
 PCC = 1283.18

Curve HA\_WBSUP-9  
 PI = 2373.4  
 DELTA = 39° 08' 20.22" (RT)  
 D = 957.2935'  
 T = 70.42'  
 L = 103.92'  
 R = 600.00'  
 PC = 2302.69  
 PT = 2406.51

Curve HA\_RAMPC-2  
 PI = 15297.3  
 DELTA = 94° 21' 05.28" (RT)  
 D = 2504.25'  
 T = 246.55'  
 L = 376.28'  
 R = 228.50'  
 PC = 1283.18  
 PCC = 1659.47

Curve HA\_RAMPB-2  
 PI = 1442.12  
 DELTA = 50° 09' 33.43" (LT)  
 D = 1933.18'  
 T = 137.2'  
 L = 286.51'  
 R = 293.00'  
 PC = 1305.00  
 PT = 1561.50

Curve HA\_RAMPC-3  
 PI = 1905.87  
 DELTA = 94° 19' 07.77" (RT)  
 D = 2504.29'  
 T = 246.41'  
 L = 376.15'  
 R = 228.50'  
 PC = 1659.47  
 PCC = 2035.62

Curve HA\_WBSUP-11  
 PI = 2997.90  
 DELTA = 121° 45' 56.74" (LT)  
 D = 7137.11'  
 T = 143.63'  
 L = 170.02'  
 R = 80.00'  
 PC = 2854.27  
 PT = 3024.29

**REFERENCES**  
 (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)

Construction Alignment Data IG(1)-IG(4)	
Typical Sections	2B
Route 7 EB & WB Profile	6A
Shared Use Path Profiles	6A(1)
Ramp Profiles	6A(2)
Utility Owners	IE
Property Owners	IE

**LEGEND**

	Proposed Pavement Milling and Overlay		Denotes Construction Limits In Cuts
	Proposed Full Depth Pavement		Denotes Construction Limits In Fills
	Demolition of Pavement		

Potential Material Laydown Area (to be graded and permanently stabilized prior to contract completion)



PROJECT	SHEET NO.
0007-029-139	6C

3/16/2015


PROJECT MANAGER: *Acting Babman, PE* (703) 259-1940 (Nava, District)  
 SURVEYED BY, DATE: *Woolpert, Inc.* February 6, 2013  
 DESIGN BY: *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE: *Woolpert, Inc.* January 22, 2013

THESE PLANS ARE UNFINISHED  
 AND UNAPPROVED AND ARE NOT  
 TO BE USED FOR ANY TYPE  
 OF CONSTRUCTION OR THE  
 ACQUISITION OF RIGHT OF WAY.

ADDITIONAL EASEMENTS FOR UTILITY  
 RELOCATIONS MAY BE REQUIRED  
 BEYOND THE PROPOSED RIGHT-OF-  
 WAY SHOWN ON THESE PLANS.

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	6D

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



Curve HA\_EBSUPBR-1  
 PI • 0-59.71  
 DELTA • 34° 54' 14.7" (RT)  
 D • 38' 11" 50"  
 T • 47.16'  
 L • 91.38'  
 R • 150.00'  
 PC • 0-12.55  
 PCC • 1-03.93  
 PT • 1-03.93

Curve HA\_EBSUPBR-5  
 PI • 8-01.51  
 DELTA • 41° 27' 12.46" (RT)  
 D • 139' 44' 45"  
 T • 15.51'  
 L • 29.66'  
 R • 41.00'  
 PC • 7-86.00  
 PT • 8-15.66

Curve HA\_RTENTR-3  
 PI • 4-12.18  
 DELTA • 71° 00' 12.78" (LT)  
 D • 57' 17' 45"  
 T • 71.33'  
 L • 123.92'  
 R • 100.00'  
 PC • 3-40.84  
 PT • 4-64.77

Curve HA\_RAMPD-1  
 PI • 28-57.08  
 DELTA • 22° 34' 46.23" (LT)  
 D • 16' 12' 14"  
 T • 70.59'  
 L • 139.35'  
 R • 353.59'  
 PC • 27-86.49  
 PT • 29-25.83

Curve HA\_EBSUPBR-6  
 PI • 9-76.19  
 DELTA • 89° 46' 27.32" (LT)  
 D • 139' 44' 45"  
 T • 40.84'  
 L • 64.24'  
 R • 41.00'  
 PC • 9-35.35  
 PT • 09-99.59

Curve HA\_EBSUPBR-7  
 PI • 10-57.24  
 DELTA • 25° 28' 34.14" (RT)  
 D • 54' 34' 03"  
 T • 23.74'  
 L • 46.69'  
 R • 105.00'  
 PC • 10-33.50  
 PRC • 10-80.19

Curve HA\_EBSUPBR-2  
 PI • 1-43.42  
 DELTA • 66° 42' 10.52" (RT)  
 D • 95' 29' 35"  
 T • 39.49'  
 L • 69.85'  
 R • 60.00'  
 PCC • 1-03.93  
 PT • 1-73.78

Curve HA\_EBSUPBR-3  
 PI • 5-06.76  
 DELTA • 142° 58' 14.92" (LT)  
 D • 76' 23' 40"  
 T • 223.96'  
 L • 187.15'  
 R • 75.00'  
 PC • 2-82.80  
 PT • 4-69.95

Curve HA\_EBSUPBR-4  
 PI • 5-54.38  
 DELTA • 38° 52' 56.06" (RT)  
 D • 76' 23' 40"  
 T • 26.47'  
 L • 50.90'  
 R • 75.00'  
 PC • 5-27.91  
 PT • 5-78.81

Curve HA\_RAMPE-2  
 PI • 44-96.73  
 DELTA • 71° 15' 13.18" (RT)  
 D • 22' 56' 58"  
 T • 178.92' Ines  
 L • 310.48'  
 R • 249.66'  
 PCC • 43-17.81  
 PT • 46-28.29

Curve HA\_RTENTR-1  
 PI • 0-88.95  
 DELTA • 48° 49' 36.1" (RT)  
 D • 92' 24' 45"  
 T • 28.14'  
 L • 52.84'  
 R • 62.00'  
 PC • 0-60.81  
 PT • 1-13.64

**REFERENCES**  
 (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)

Construction Alignment Data IG(1)-IG(4)	2B
Typical Sections	2B
Route 7 EB & WB Profile	6A
Shared Use Path Profiles	6A(1)
Ramp Profiles	6A(2)
Radio Tower Profile	6A(3)
Utility Owners	1E
Property Owners	1E

- LEGEND**
- Proposed Pavement Milling and Overlay
  - Proposed Full Depth Pavement
  - Demolition of Pavement
  - Potential Material Laydown Area (to be graded and permanently stabilized prior to contract completion)
  - Denotes Construction Limits In Cuts
  - Denotes Construction Limits In Fills



PROJECT MANAGER: Actiur Babman, PE (703) 259-1940 (Nova District)  
SURVEYED BY, DATE: Woolpert, Inc., February 6, 2013  
DESIGN BY: Blinker Design Associates  
SUBSURFACE UTILITY BY, DATE: Woolpert, Inc., January 22, 2013


THESE PLANS ARE UNFINISHED AND UNAPPROVED AND ARE NOT TO BE USED FOR ANY TYPE OF CONSTRUCTION OR THE ACQUISITION OF RIGHT OF WAY.

**LEGEND**

- Proposed Pavement Milling and Overlay
- Proposed Full Depth Pavement
- Demolition of Pavement

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	7

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.

**REFERENCES**  
(PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)

Construction Alignment Data	IG(1)-IG(4)
Typical Sections	2B
Route 7 EB & WB Profile	7A
Shared Use Path Profiles	7A(1)
Ramp Profiles	7A(2)
Utility Owners	1E
Property Owners	1E





PROJECT	SHEET NO.
0007-029-139	7

PROJECT MANAGER Act'ur Babman, PE (703) 259-1940 (Nava District)  
 SURVEYED BY, DATE Woolpert, Inc. February 6, 2013  
 DESIGN BY Blinker Design Associates  
 SUBSURFACE UTILITY BY, DATE Woolpert, Inc. January 22, 2013


REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	7A

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer



541+00.00      542+00.00      543+00.00      544+00.00      545+00.00      546+00.00      547+00.00      548+00.00






PROJECT 0007-029-139 SHEET NO. 7A

PROJECT MANAGER *Act'ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	7A(1)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Blinker Design Associates, P.C.  
 Glen Allen, Virginia  
 CMI Engineer




PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	7A(2)

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT


Blinker Design Associates, P.C.  
Glen Allen, Virginia  
Civil Engineer



PROJECT MANAGER: Act'ur Babman, PE (703) 259-1940 (L'noxia\_District)  
SURVEYED BY, DATE: Woolpert, Inc. February 6, 2013  
DESIGN BY: Blinker Design Associates  
SUBSURFACE UTILITY BY, DATE: Woolpert, Inc. January 22, 2013

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	8

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



ADDITIONAL EASEMENTS FOR UTILITY RELOCATIONS MAY BE REQUIRED BEYOND THE PROPOSED RIGHT-OF-WAY SHOWN ON THESE PLANS.

**LEGEND**

	Proposed Pavement Milling and Overlay		Denotes Construction Limits in Cuts
	Proposed Full Depth Pavement		Denotes Construction Limits in Fills


**WAGMAN**  
BRIDGING GENERATIONS - SINCE 1902

**FOR INFORMATION ONLY**

**rd**

REFERENCES (PROFILES, DETAIL & DRAINAGE DESCRIPTION SHEETS, ETC.)

Construction Alignment Data (IG1-IG4)	
Typical Section	2B
Route 7 EB & WB Profile	8A
Utility Owners	1E
Property Owners	1E



PROJECT	SHEET NO.
0007-029-139	8

PROJECT MANAGER *Actur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc. February 6, 2013*  
 DESIGN BY *Rinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc. January 22, 2013*

REVISED	STATE	ROUTE	STATE PROJECT	SHEET NO.
	VA.	7	0007-029-139, C501, R201, P101	8A


DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

Rinker Design Associates, P.C.  
 Glen Allen, Virginia  
 Civil Engineer



WBL STA 548+00 TO END OF PROJECT


Existing Ground



EBL STA 548+00 TO END OF PROJECT

Existing Ground

548+00.00      549+00.00      550+00.00      551+00.00      552+00.00



PROJECT 0007-029-139 SHEET NO. 8A

PROJECT MANAGER *Act/ur Babman, PE (703) 259-1940 (Nava District)*  
 SURVEYED BY, DATE *Woolpert, Inc.: February 6, 2013*  
 DESIGN BY *Blinker Design Associates*  
 SUBSURFACE UTILITY BY, DATE *Woolpert, Inc.: January 22, 2013*

REVISED	STATE	STATE PROJECT		SHEET NO.
		ROUTE		
	VA.	7	0007-029-139, C501, R201, P101	2A

# TYPICAL SECTIONS

## West of Bridge Over Dulles Toll Road and Dulles Airport Access Road

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT





**PAVEMENT SECTION**  
**New Pavement and Pavement Widening**  
 Surface - 2" Asphalt Concrete, Type SM-9.5D (estimated at 236 lbs/sq.yd.)  
 Intermediate - 2" Asphalt Concrete, Type IM-19.0A (estimated at 236 lbs/sq.yd.)  
 Base - 8" Asphalt Concrete, Type BM-25.0A  
 Subbase - 6" Aggregate Base Material, Type 1, Size 21B. The subbase should be extended one (1) foot behind the curb and gutter and connected to a standard UD-4 edgedrain, in accordance with UD-4 standard details.

**Mill and Overlay**  
 For salvage/build-up areas, the existing pavement shall be milled two (2) inches and replaced with the following:  
 Surface - 2" Asphalt Concrete, Type SM-9D (estimated at 236 lbs/sq.yd.)  
 Intermediate - 2" Asphalt Concrete, Type IM-19.0A (estimated at 236 lbs/sq.yd.)

**Shared-Use Path**  
 Surface - 2" Asphalt Concrete, Type SM-9.5A (estimated at 236 lbs/sq.yd.)  
 Subbase - 6" Aggregate Base Material, Type 1, Size No. 21B, extended a minimum of 6' beyond the edges of asphalt pavement.

**Hydraulic Cement Concrete Sidewalks**  
 Surface - 4" Class A3 Hydraulic Cement Concrete  
 Subbase - 4" Aggregate Base Material Type 1, Size No. 21A, extended 6' on either side of the surface material.

**Temporary Pavement**  
 All temporary pavement designs shall have a minimum six (6) inches of asphalt concrete and shall meet the following minimum design criteria:  
 -Design Life - six (6) months minimum  
 -Reliability - eighty-five percent (85%) minimum  
 -Initial Serviceability - 4.2 minimum  
 -Terminal Serviceability - 2.8 minimum  
 -Standard Deviation - 0.49 minimum  
 -CBR value for the subgrade soils determined laboratory tests



- NOTES:**
1. SR'd. UD-4 underdrains shall be placed under curb/curb & gutter on low side of roadway for mainline and ramps.
  2. Underdrains for the shared use path will be evaluated by the Geotechnical Engineer in accordance with the applicable standards.
  3. SR'd. UD-2 shall be placed under raised grass medians.
  4. All paved shoulders shall have mainline pavement (mainline and ramps)
  5. Shared Use Path Typical Sections (especially in a cut) will need to be modified after drainage analysis and design is completed.
  6. Where guardrail is required widen shoulder 3'.
  7. CG-2 style curb to be used west of Jarett Valley Drive. CG-3 style curb to be used east of Jarett Valley Drive.



TYPICAL SECTIONS (1)		
PROJECT	0007-029-139	SHEET NO.
		2A

PROJECT MANAGER *Act/ur Babman, EE (703) 259-1940 (Nava District)*  
SURVEYED BY, DATE *Woolpert, Inc.: February 6, 2013*  
DESIGN BY *Blinker Design Associates, P.C.*  
SUBSURFACE UTILITY BY, DATE *Woolpert, Inc.: January 22, 2013*



**THESE PLANS ARE UNFINISHED  
AND UNAPPROVED AND ARE NOT  
TO BE USED FOR ANY TYPE  
OF CONSTRUCTION OR THE  
ACQUISITION OF RIGHT OF WAY.**

# TYPICAL SECTIONS


## East of Bridge Over Dulles Toll Road and Dulles Airport Access Road

REVISED	STATE	STATE PROJECT		SHEET NO.
		ROUTE	PROJECT	
	VA.	7	0007-029-139, C501, R201, P101	2B

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



\*WBL Transition to 11' Between STA 542+00.00 and STA 543+00.00  
EBL Transition to 11' Between STA 539+82.55 and STA 543+52.25  
\*\* Milling of WBL ends at STA 542+94.59



STA 537+54.58 to STA 539+57.23

- NOTES:**
1. S'd UD-4 underdrains shall be placed under curb/curb & gutter on low side of roadway for mainline and ramps.
  2. Underdrains for the shared use path will be evaluated by the Geotechnical Engineer in accordance with the applicable standards.
  3. S'd UD-2 shall be placed under raised grass medians.
  4. All paved shoulders shall have mainline pavement (mainline and ramps)
  5. Shared Use Path Typical Sections (especially in a cut) will need to be modified after drainage analysis and design is completed.
  6. Where guardrail is required widen shoulder 3'.
  7. CG-2 style curb to be used west of Jarett Valley Drive.  
CG-3 style curb to be used east of Jarett Valley Drive.



TYPICAL SECTIONS (2)		
PROJECT	0007-029-139	SHEET NO.
		2B











THESE PLANS ARE UNFINISHED  
 AND UNAPPROVED AND ARE NOT  
 TO BE USED FOR ANY TYPE  
 OF CONSTRUCTION OR THE  
 ACQUISITION OF RIGHT OF WAY.

# TYPICAL SECTIONS


## Ramps and Shared Use Paths

REVISED	STATE	STATE PROJECT		SHEET NO.
		ROUTE	PROJECT	
	VA.	7	0007-029-139, C501, R201, P101	2C

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT



- NOTES:**
- S'd. UD-4 underdrains shall be placed under curb/curb & gutter on low side of roadway for mainline and ramps.
  - Underdrains for the shared use path will be evaluated by the Geotechnical Engineer in accordance with the applicable standards.
  - S'd. UD-2 shall be placed under raised grass medians.
  - All paved shoulders shall have mainline pavement (mainline and ramps)
  - Shared Use Path Typical Sections (especially in a cut) will need to be modified after drainage analysis and design is completed.
  - Where guardrail is required widen shoulder 3'.
  - CG-2 style curb to be used west of Jarett Valley Drive. CG-3 style curb to be used east of Jarett Valley Drive.



TYPICAL SECTIONS (3)		
PROJECT	0007-029-139	SHEET NO.
		2C



Volume II



STATE	FEDERAL AID	STATE	SHEET NO.
VA.	PROJECT	ROUTE	PROJECT
		7	0007-029-139, B617, B618
NBIS Number: 000000000006246 000000000006248		UPC No.	82135
Federal Oversight Code: -		FHWA Construction and Scour Code:	X231-SN

DESIGN EXC **WAGMAN** **rda** **WR&A**  
BRIDGING GENERATIONS · SINCE 1902

**GENERAL NOTES:**

None.

The original approved sheet, including original signatures, is filed in the VDOT Central Office. Any misuse of electronic files, including scanned signatures is illegal. Violators will be prosecuted to the full extent of the applicable laws.

Width: 14'-0" SUP, 51'-0" roadway, 16'-0" median, 51'-0" roadway, 14'-0" SUP. Overall width 147'-8" face-to-face of rails.

Span layout: 58' - 80' - 80' - 80' - 80' - 58' continuous steel plate girder spans.

Capacity: HS20-44 loading and alternate military loading for existing piers.  
HL-93 loading for new superstructure, abutments, and new piers.

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2007.

Design: AASHTO LRFD Bridge Design Specifications, 6th Edition, 2012; and VDOT Modifications.  
AASHTO Standard Specifications for Highway Bridges, 16th Edition, 1996; 1997 and 1998 Interim Specifications; and VDOT modifications.

Standards: Virginia Department of Transportation Road and Bridge Standards, 2008.





These plans are incomplete unless accompanied by the Supplemental Specifications and Special Provisions included in the contract documents.

This project shall be constructed in accordance with the Virginia Department of Transportation Work Area Protection Manual, June 2011 and latest revisions.

Bridge No. of existing bridges are 1132 and 1133 and Plan No. is 189-08 and 189-08A.

These plans are prepared based on survey and the information shown on the As-Built bridge plans No. 189-08 and 189-08A. A copy of the As-Built Plans can be obtained from VDOT - Northern VA District Structure and Bridge Section.

The existing structure is designated a Type B structure in accordance with Sec. 411.



RECOMMENDED FOR APPROVAL FOR CONSTRUCTION
VDOT PROJECT MANAGER
DISTRICT CONSTRUCTION MANAGER
WHITMAN REQUARDT & ASSOCIATES RICHMOND, VA STRUCTURAL ENGINEER
PLANS BY: WRA
COORDINATED: xxx
SUPERVISED: Jeremy Schlusel
DESIGNED: David Nizamoff
DRAWN: David Nizamoff
CHECKED: James Guinther

Legend:  
SUP - Shared Use Path  
\* - Minimum horizontal clearance  
\*\* - Width including shoulders

**PRELIMINARY PLANS**  
THESE PLANS NOT TO BE USED FOR CONSTRUCTION

No.	Description	Date
REVISIONS		
For Table of Revisions, see Sheet 2.		

Note:  
The bridge plan has been oriented to match the roadway stationing. The substructure designation in this plan has been reversed in relation to the As-built bridge plans.


**VDOT**  
**COMMONWEALTH OF VIRGINIA**  
**DEPARTMENT OF TRANSPORTATION**

PROPOSED BRIDGE WIDENING ON  
RTE. 7 OVER DULLES TOLL ROAD  
AND AIRPORT ACCESS HIGHWAY  
FAIRFAX COUNTY - 1.9 MI. W. INT. RTE. 495  
PROJ. 0007-029-139, B617, B618

Recommended for Approval: \_\_\_\_\_ Date \_\_\_\_\_  
D.B. Project Manager


Approved: \_\_\_\_\_ Date \_\_\_\_\_  
Chief Engineer

Date: March 9, 2015 © 2015, Commonwealth of Virginia Sheet 1 of 9



EXISTING TRANSVERSE SECTION

Note:  
Existing bridge dimensions shown are from as-built plans.



PROPOSED TRANSVERSE SECTION

\* WB lane arrows shown for future lane configuration.

WHITMAN REQUARDT & ASSOCIATES  
RICHMOND, VA  
STRUCTURAL ENGINEER


- Legend:
- Existing structure
  - New structure
  - C.J. = construction joint

**PRELIMINARY PLANS**  
THESE PLANS NOT TO BE USED FOR CONSTRUCTION


COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION			
STRUCTURE AND BRIDGE DIVISION			
<b>TRANSVERSE SECTION</b>			
Designed: DAN	Date	Plan No.	Sheet No.
Drawn: DAN	MAR. 2015	189-08B	2 OF 9
Checked: JAG			









PLAN



ELEVATION




DEMOLITION




PROPOSED

PIER END RECONSTRUCTION DETAIL

Scale: 3/8" = 1'-0"



SECTION A-A  
TYPICAL NEW PIER  
Scale: 3/8" = 1'-0"



SECTION B-B  
TYPICAL PIER MODIFICATION  
Scale: 3/8" = 1'-0"

Note:  
Pier 3 has fixed bearings. Dowels will be designed for longitudinal forces at fixed pier.

- Legend:
- Existing structure
  - Demo structure
  - Completed structure

**PRELIMINARY PLANS**  
THESE PLANS NOT TO BE USED FOR CONSTRUCTION

COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION			
STRUCTURE AND BRIDGE DIVISION			
<b>TYPICAL PIER MODIFICATIONS</b>			
Designed: DAN.....	Date	Plan No.	Sheet No.
Drawn: DAN.....	MAR. 2015	189-08B	4 of 9
Checked: JAR.....			

b18908B005.dgn













Volume II



ABBREVIATIONS


A/C	Address Comments	SFA	Submit for Approval
R/A	Review and Approve	SFC	Submit for Comment
R/C	Review and Comment	FRPS	Form, Rebar, Pour, Strip






ABBREVIATIONS

A/C Address Comments  
 R/A Review and Approve  
 R/C Review and Comment  
 SFA Submit for Approval  
 SFC Submit for Comment  
 FRPS Form, Rebar, Pour, Strip



ABBREVIATIONS

A/C Address Comments  
 R/A Review and Approve  
 R/C Review and Comment  
 SFA Submit for Approval  
 SFC Submit for Comment  
 FRPS Form, Rebar, Pour, Strip




ABBREVIATIONS

A/C	Address Comments	SFA	Submit for Approval
R/A	Review and Approve	SFC	Submit for Comment
R/C	Review and Comment	FRPS	Form, Rebar, Pour, Strip







ABBREVIATIONS

A/C	Address Comments	SFA	Submit for Approval
R/A	Review and Approve	SFC	Submit for Comment
R/C	Review and Comment	FRPS	Form, Rebar, Pour, Strip

Activity ID	Activity Name	Planned Duration	Start	Finish	Calendar	Total Float	2015												2016												2017											
							Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct								
<b>BMP #2</b>																																										
A9810	E/S	4.0d	16-Dec-16	22-Dec-16	Workweek Weather	146.0d																																				
A9820	Clear/ Grub	7.0d	22-Dec-16	05-Jan-17	Workweek Weather	146.0d																																				
A9830	Access	7.0d	05-Jan-17	16-Jan-17	Workweek Weather	146.0d																																				
A9840	Construct Basin	15.0d	16-Jan-17	06-Feb-17	Workweek Weather	146.0d																																				
<b>Phase 3</b>																																										
A9490	Pier 1 MOT	2.0d	15-Mar-17	16-Mar-17	Workweek Weather	0.0d																																				
A9530	Pier 5 MOT	2.0d	17-Mar-17	20-Mar-17	Workweek Weather	98.9d																																				
A9510	Pier 3 MOT	2.0d	29-Mar-17	30-Mar-17	Workweek Weather	0.0d																																				
A9520	Pier 4 MOT	2.0d	31-Mar-17	03-Apr-17	Workweek Weather	98.9d																																				
A9500	Pier 2 MOT	2.0d	12-Apr-17	13-Apr-17	Workweek Weather	0.0d																																				
<b>Bridge</b>																																										
A6940	Remove Exist. Superstr.	15.0d	01-Mar-17	21-Mar-17	Workweek Weather	0.0d																																				
<b>Abutments</b>																																										
A6950	SOE Abut A	5.0d	22-Mar-17	28-Mar-17	Workweek Weather	61.9d																																				
A6960	SOE Abut B	5.0d	22-Mar-17	28-Mar-17	Workweek Weather	61.9d																																				
A6970	Rem. Portion of Abut. A	5.0d	29-Mar-17	04-Apr-17	Workweek Weather	61.9d																																				
A6980	Rem. Portion of Abut. B	5.0d	29-Mar-17	04-Apr-17	Workweek Weather	61.9d																																				
A6990	Drive Pile Abut. A	5.0d	05-Apr-17	11-Apr-17	Workweek Weather	61.9d																																				
A7000	Drive Pile Abut. B	5.0d	05-Apr-17	11-Apr-17	Workweek Weather	61.9d																																				
A7010	Retaining Wall Structure Abut. A	20.0d	12-Apr-17	09-May-17	Workweek Weather	61.9d																																				
A7020	Retaining Wall Structure Abut. B	20.0d	12-Apr-17	09-May-17	Workweek Weather	61.9d																																				
A7030	FRPS Abut. A Footing	6.0d	10-May-17	17-May-17	Workweek Weather	61.9d																																				
A7040	FRPS Abut. B Footing	6.0d	10-May-17	17-May-17	Workweek Weather	61.9d																																				
A7050	FRPS Abut. A Seat	6.0d	18-May-17	25-May-17	Workweek Weather	61.9d																																				
A7060	FRPS Abut. B Seat	6.0d	18-May-17	25-May-17	Workweek Weather	61.9d																																				
A7070	Coping Abut. A	7.0d	26-May-17	06-Jun-17	Workweek Weather	61.9d																																				
A7080	Coping Abut. B	7.0d	26-May-17	06-Jun-17	Workweek Weather	61.9d																																				
<b>Piers</b>																																										
A7190	Rehab Pier 1	8.0d	17-Mar-17	28-Mar-17	Workweek Weather	0.0d																																				
A7230	Rehab Pier 5	8.0d	21-Mar-17	30-Mar-17	Workweek Weather	98.9d																																				
A7210	Rehab Pier 3	8.0d	31-Mar-17	11-Apr-17	Workweek Weather	0.0d																																				
A7220	Rehab Pier 4	8.0d	04-Apr-17	13-Apr-17	Workweek Weather	98.9d																																				
A7200	Rehab Pier 2	8.0d	14-Apr-17	25-Apr-17	Workweek Weather	0.0d																																				
<b>Superstructure</b>																																										
A7240	Erect Girders	10.0d	26-Apr-17	09-May-17	Workweek Weather	0.0d																																				
A7250	Install Overhangs	12.0d	01-May-17	16-May-17	Workweek Weather	0.0d																																				
A9690	FRPS Integral Backwall A	8.0d	10-May-17	19-May-17	Workweek Weather	0.0d																																				
A7260	SIP Deck Forms	5.0d	17-May-17	23-May-17	Workweek Weather	0.0d																																				
A7270	Deck Rebar	6.0d	24-May-17	01-Jun-17	Workweek Weather	0.0d																																				
A9700	FRPS Integral Backwall B	8.0d	22-May-17	01-Jun-17	Workweek Weather	0.0d																																				
A7280	Pour Deck	5.0d	02-Jun-17	08-Jun-17	Workweek Weather	0.0d																																				
A7290	Deck Curing	5.0d	09-Jun-17	15-Jun-17	Workweek Weather	0.0d																																				
A9710	FRPS Approach Slab A	5.0d	09-Jun-17	15-Jun-17	Workweek Weather	18.0d																																				
A9720	FRPS Approach Slab B	5.0d	16-Jun-17	22-Jun-17	Workweek Weather	18.0d																																				
A7300	FRPS Parapet	6.0d	16-Jun-17	23-Jun-17	Workweek Weather	0.0d																																				
A7310	Install Railing	5.0d	26-Jun-17	30-Jun-17	Workweek Weather	0.0d																																				
A7320	Install Fence	5.0d	03-Jul-17	10-Jul-17	Workweek Weather	0.0d																																				
A9170	Strip Overhangs	7.0d	11-Jul-17	19-Jul-17	Workweek Weather	0.0d																																				
A7330	Groove Deck	2.0d	20-Jul-17	21-Jul-17	Workweek Weather	0.0d																																				
<b>Roadway Rt. 7 EBL</b>																																										
A9140	Bridge Tie-Ins	8.0d	24-Jul-17	02-Aug-17	Workweek Weather	0.0d																																				
A9030	Stripe/Switch Traffic to Phase 4	3.0d	03-Aug-17	07-Aug-17	Workweek Weather	0.0d																																				
<b>Sta. 522+00 to 530+99 (West of Bridge)</b>																																										
A8020	Clear and Grub	5.0d	01-Mar-17	07-Mar-17	Workweek Weather	23.0d																																				
A8040	Saw Cut	3.0d	08-Mar-17	10-Mar-17	Workweek Weather	23.0d																																				
A8030	E/S	5.0d	08-Mar-17	14-Mar-17	Workweek Weather	23.0d																																				
A8050	Strip Topsoil	3.0d	13-Mar-17	15-Mar-17	Workweek Weather	23.0d																																				
A8070	Rough Grade	15.0d	16-Mar-17	05-Apr-17	Grading	23.0d																																				
A8060	Storm Sewer	15.0d	06-Apr-17	26-Apr-17	Grading	23.0d																																				
A8100	Underdrain	5.0d	27-Apr-17	03-May-17	Grading	23.0d																																				
A8080	Fine Grade	7.0d	04-May-17	12-May-17	Grading	23.0d																																				
A8110	Subbase	5.0d	15-May-17	19-May-17	Grading	23.0d																																				
A8120	Curb & Gutter	7.0d	19-May-17	31-May-17	Workweek Weather	22.1d																																				
A8130	BM	5.0d	01-Jun-17	07-Jun-17	Paving	22.0d																																				
A8140	IM	5.0d	08-Jun-17	14-Jun-17	Paving	22.0d																																				
A8160	Dress Shoulder	5.0d	14-Jun-17	21-Jun-17	Workweek Weather	21.1d																																				
A8170	Seed	3.0d	21-Jun-17	26-Jun-17	Workweek Weather	21.1d																																				
A8180	Guardrail	5.0d	26-Jun-17	03-Jul-17	Workweek Weather	21.1d																																				
<b>Sta. 535+36 to 547+21 (East of Bridge)</b>																																										
A8190	Clear and Grub	5.0d	01-Mar-17	07-Mar-17	Workweek Weather	13.0d																																				
A8210	Saw Cut	3.0d	08-Mar-17	10-Mar-17	Workweek Weather	13.0d																																				



ABBREVIATIONS

- A/C Address Comments
- R/A Review and Approve
- R/C Review and Comment
- SFA Submit for Approval
- SFC Submit for Comment
- FRPS Form, Rebar, Pour, Strip



